


DAY-79 #100DAYSOFRTL


Aim:- Implementation of SR FLIPFLOP TO RANDOM XY FLIPFLOP.



RTL CODE:-

```
////DATE:-19/03/2024
   !///DAY-79
   '///Implementation of SR Flipflop TO Random XY Flipflop
   module Day_79(input clk,rst,X,Y, output q,qbar);
   wire w1,w2;
|xor g1(w1, X, qbar);
o and g2(w2,Y,q);
   SRff Srff(clk,rst,w1,w2,q,qbar);
   endmodule
   module SRff(input clk,rst,S,R,
   output reg q,
   output qbar);
o lalways@(posedge clk) begin
o lif(rst) q<=0;</pre>
   else begin
O case({S,R})
O 2'b00:q<=q; ///No change
O 2'b01:q<=0; ///reset
O 2'b10:q<=1; ///set
   endcase
   end
   end
O assign qbar=~q;
   endmodule
```

WAVEFORMS:-



TESTBENCH:-

SCHEMATIC:-

